



HAL
open science

On Sanskrit commentaries dealing with mathematics (Vth-XIIth century)

Agathe Keller

► **To cite this version:**

Agathe Keller. On Sanskrit commentaries dealing with mathematics (Vth-XIIth century). 2007.
halshs-00189339v3

HAL Id: halshs-00189339

<https://shs.hal.science/halshs-00189339v3>

Preprint submitted on 22 Jul 2009 (v3), last revised 24 Aug 2009 (v4)

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

On Sanskrit commentaries dealing with mathematics (fifth-twelfth century)*

Agathe Keller

Abstract

The diversity of past readings on Sanskrit commentaries dealing with mathematics by studying texts composed between the fifth and the twelfth century A. D. Their collection in libraries, the way they were consequently studied by historians of mathematics, and a close reading of the commentaries themselves opens new perspectives on the diversity of mathematical texts and practices as much as on the history of positional arithmetics in India.

Cet article examine les différentes types de lectures portées, par le passé, sur les commentaires mathématiques en langue Sanskrite rédigés entre le VIIème et le XIIème siècle après J. -C. Nous nous demanderons comment ces textes ont été réunis dans des bibliothèques puis comment ils ont été étudiés par des historiens des mathématiques. L'étude de la relation du commentaire à ce qu'il commente ouvre des perspectives nouvelles tant pour l'histoire des différentes pratiques mathématiques et textuelles que pour l'histoire de l'arithmétique positionnelle en Inde.

*I would like to thank K. Chemla, F. Bretelle, C. Proust for their remarks on several drafts of this article.

Introduction

A renewed interest for contextualization in indological studies¹, is but slowly affecting publications on Indian mathematics. This remoteness of history of mathematics within the general field of indology is partly due to a lively historiographical trend of technical and patriotic history of mathematics which remains oblivious to social science. However, there is indeed little information on the context in which mathematics and astronomy were practiced in India in the past². To overcome this problem some historians of science have turned to periods (XVIth-XIXth century) and places where institutions, libraries and many texts help us contextualize their mathematical and astronomical ideas³.

I would like to argue that a focus on the kind of texts produced by astronomers and mathematicians of the Indian subcontinent and the history of how they were transmitted to us can also help us contextualize the knowledge they disclose. Taking in account the diverse textual forms that were produced, trying to understand the function they had, their self-proclaimed aim as well as what they show us of their own conceptions of mathematical practices and ideas can provide information on who produced mathematical texts, why they were produced and how they were used⁴. This approach can also be fruitful for the history of mathematical practices and conceptions in India as elsewhere⁵. These questions can be addressed to texts of earlier periods for which very little background information is known.

Such a focus on text implies a clarification of what manuscripts can be found in libraries today, as they are the sources of editions and studies. Springs here many questions⁶: Who copied the texts now at our disposal? Who had them copied? How were these texts used and read? How where these texts collected into libraries? A set of questions that C. Minkowski and D. Raina address more directly in their contributions to this volume.

This paper examines the specific case of commentaries on mathematical subjects written in Sanskrit between the fifth and the twelfth century A. D.⁷ with the overall aim to understand the function assigned to commentaries on mathematics. The focus of this study will therefore be on how commentaries were related to the texts they were commenting. This study scrutinizes the point of view of different sets

¹Proeminently in the project headed by Sheldon Pollock, "Sanskrit Knowledge Systems at the Eve of Colonialism" (SKEC). See <http://www.columbia.edu/itc/mealac/pollock/sks>, (Pollock, 2002) and the outcome for literature (Pollock, 2006).

²(Plofker, 2009) struggles as she tries link a technical history to social questions, but both fields remain remote to another today.

³Among the publications on history of science, produced within Pollock's SKEC, see the works of Christopher Minkowski and Dominik Wujastyk, listed at <http://www.columbia.edu/itc/mealac/pollock/sks/papers/index.html> We may add to this the recently defended thesis of Toke Lindegaard Knudsen, (Knudsen, 2008).

⁴A list of various categories of astronomical/astrological texts is given in (Pingree, 1981), and reformulated in (Plofker, 2009). Different kinds of texts have thus long been identified, with a list of subjects or styles they are likely to adopt. Kim Plofker (p. 105-108) briefly evokes the kind of trigonometrical astronomy stated in *karaṇas* as opposed to those given in *siddhāntas*. Mathematical difference and textual differences are noted, but not closely related. Remark that both kind of texts were commented upon.

⁵K. Chemla has extensively published on the question. Her latest synthesis is (Chemla, 2004).

⁶A similar set of questions addressed to another kind of texts, colonial archives, can be found in (Stoler, 2002).

⁷Precisely: commentaries written between the seventh and twelfth century on texts composed between the fifth and eighth century.

of actors: those who wrote commentaries, those who had them copied and those who analyzed them as historians of mathematics. The question of whether there was a continuity between these different attitudes will be raised. Were commentaries on mathematics considered as an adherent whole text? Were they thought of as re-disposable pieces of a puzzle to be used when useful, in understanding an algorithm or an idea? In other words, this analysis will attempt to grasp the kind of readings required overtime from a commentary in India.

A first part will examine what is known today on commentaries on mathematics of the fifth-twelfth century, attempting to situate them in the larger context of the literature on astral science (*jyotiṣa*)⁸. Then a description of the manuscripts at our disposal will provide information on who copied them as much as how such texts were copied. A study of certain histories of mathematics in India from the XIXth century onwards, giving a special attention to the story of the rediscovery and edition of the works of Āryabhaṭa (ca. 499), Brahmagupta (ca. 628) and Śrīdhara (ca. 950), will look at how commentaries on mathematics were read in more recent times. Finally, a close look at algorithms to extract square roots, will serve as an illustration of an analysis of a mathematical text focussing on how commentaries relate to the text they comment, providing insights on the way mathematicians conceived and used the decimal place value notation.

1 Commentaries on mathematics from the fifth to the twelfth century

Indologists are overwhelmed by the number of manuscripts that are at their disposition today to make new editions. The case of astronomy and mathematics is quite exceptional in this respect, since a census has been undertaken, which enables us to evaluate the number of manuscripts and published editions for the specific field of *jyotiṣa*. Indeed, David Pingree’s *Census of the Exact Sciences in Sanskrit* (CESS)⁹ lists most of is known today of existing manuscripts on astronomy and mathematics in Sanskrit.

The near exhaustivity of the CESS, can thus enable us to reflect quantitatively on manuscripts which have been collected and preserved for astronomical, astrological or mathematical texts. Since the census not only gives manuscript references but has also tracked published editions, it can help us evaluate how many of these texts couched in manuscripts have been edited and studied in the last two hundred years.

⁸ *Jyotiṣa* (lit. “the (sky’s) luminaries”), which is conveniently translate as “astronomy” or more exactly as “astral science” is a field which includes in fact horoscopy and mathematics together with observational and computational astronomy. See (Pingree, 1981, Introduction and Table of contents).

⁹(Pingree, 1970-1995). D. Pingree started in 1955 (see CESS I, preface.) a survey of manuscripts on *jyotiṣa* that was still left unfinished when he died fifty years later in november 2005. The CESS is in 5 volumes, volume 6 is still pending. For authors that have not yet been treated in the published CESS, one can refer to (Sen, Bag, & Sarma, 1966) and to individual library catalogs. Despite it’s name, the CESS lists texts in all sorts of languages of the Indian subcontinent. David Pingree cast a large net when undertaking his census, considering texts that may refer to some part of *jyotiṣa* in passing. If remaining manuscripts certainly exist in private collections, or are un- or mis- classified in libraries, probably most known manuscripts are included in his census.

A close look at the census¹⁰ shows that mathematical texts in Sanskrit have been over-studied when looked at in the farther landscape of texts on *jyotiṣa*. Indeed, texts on mathematics are comparatively few when compared to the other censused texts¹¹, but those in Sanskrit have been much more edited, studied and translated than the texts solely concerned with astronomy or astrology¹².

Commentaries on mathematical texts, in this context, have been thus very much studied, eventhough they do not represent much of the transmitted textual tradition¹³. However, as we will see, studies have often treated them in bits and pieces, or looked at them independently from the text they comment. Furthermore, if commentaries have been edited, they have often not been entirely translated.

This specific treatment of commentaries dealing with mathematics, when looked at from the sea of all astral texts known in Sanskrit, can be found, on a lower lever, when looking closely at the texts on mathematics known for the period ranging from the fifth to twelfth century of our common era.

1.1 A limited number of known texts on mathematics.

All the presently identified texts on mathematics of the fifth to seventh century¹⁴, for which we have manuscripts are enumerated in Table 1.1.

¹⁰I counted manually the entries, as I had no electronic version of the text: the evaluation is probably fraught with errors. It can however give us a general idea of the proportions involved. The CESS has since then been partly digitalized (volumes 1, 2 and 4) on <http://books.google.com/>. I have counted texts that were manuscripts, and have thus excluded references to authors for which there is no remaining text, or texts for which exist XXth century published editions by XXth century authors and no manuscripts.

¹¹Indeed, for the 3686 texts I have recorded in the first five volumes of the CESS only 102 (2,7 %) are clearly devoted at least partly to mathematics (*gaṇita*).

¹²I did not, when I was counting, list which texts were edited and translated. However, remarking that among the 102 texts listed, an important number are in vernacular languages (oriya, tamil, notably) and have seldom been edited or even translated, I think it is safe to consider that an important part of the texts in Sanskrit concerning *gaṇita* have been edited and translated.

¹³Under 2972 authors, and 3686 texts that I have recorded devoted to *jyotiṣa*, 816 (22%) are commentaries, and 646 authors (21,7 %) are commentators. Before starting this article, I actually thought that commentaries on mathematics were altogether neglected in the historiography of science in India, and that they were on the contrary an important part of the past tradition. I indeed, mentioned this in the introduction to my book, (Keller, 2006). This was noted and criticized quite rightly by S. R. Sharma. (S. R. Sharma, 2006, p. 144).

¹⁴Some mathematical commentaries of this period are lost to us for now at least, such as Prabhākara's commentary on the *Āryabhaṭīya* (ca.sixth century) (CESS 4 227 a), and Balabhadra's (fl. eighth century) commentary to the *Brahmasphuṭasiddhānta* (CESS 4 255 a), but we have not taken them into account here.

Table 1: A list of known texts on mathematics, in Sanskrit, fifth-twelfth century.

Dates (A.D.)	Author	Title	Abbreviation
499	Āryabhaṭa	<i>Āryabhaṭīya</i> (Chapter 2)	Ab
628	Brahmagupta	<i>Brahmasphuṭasiddhānta</i> (Chapter XII)	BSS
629	Bhāskara	<i>Āryabhaṭīyabhāṣya</i> (Chapter 2)	BAB
VIIth-Xth century	unknown	<i>Bhakhālī</i> manuscript	BM
ca 864	Pr̥thudakśvamin	<i>Vāsanābhāṣya</i> on the BSS (verses of Chapter XII)	PBSS
850-950	Śrīdhara	<i>Pāṭīgaṇita</i>	PG
idem	idem	<i>Triśatika</i> ^a	T
tenth century	Mahāvīra	<i>Gaṇitasārasaṃgraha</i>	GSS
c. 1039 A.D.	Śrīpati	<i>Gaṇitatilaka</i>	GT
ca. 1040	Someśvara	on the <i>Āryabhaṭīya</i> (chapter 2)	SAB
ca. 1150	Bhāskara II	<i>Līlāvati</i>	L
idem	idem	<i>Bijagaṇita</i>	BG
[IXth-twelfth century	Āryabhaṭa II	<i>Mahāsiddhānta</i> (Chapters XV and XVIII)	MS] ^b
ca. 1200	Sūryadeva Yajvan	on the <i>Āryabhaṭīya</i> (Chapter 2)	SYAB
[Unknown ^c	Unknown	commentary on the <i>Pāṭīgaṇita</i>	APG]

^a Admitting with [Hayashi 1995] that we do not have any extant manuscript of his *Gaṇitapañcaviṃśī*.

^b For André Billard ((Billard, 1971, 161)), the *Mahāsiddhānta* contains observational data that was made in the first half of the sixteenth century. Generally however, Āryabhaṭa II is considered to have lived between Śrīdhara and Bhāskara II (CESS I-II53). Thus the text is optionally added to this list.


^c Shukla who edited the text, considers that the commentary bears features of texts of the time span we have chosen, such as the Bhakhālī Manuscript and the BSS. (K. S. Shukla, 1959, xxviii-xxxiv).

The seventh to twelfth century is the beginning of an expanding mathematical and astronomical tradition, which will permeate not only the Indian subcontinent but extend in the East to China and in the West to the Arabic peninsula¹⁵.

If the number of mathematical texts transmitted is limited, they strike by their diversity. This maybe partly due to the tense autonomy of mathematics (*gaṇita*, “computation”) in respect to astronomy. Indeed, a number of preserved texts on mathematics belong to astronomical treatises. Mathematics

¹⁵We have chosen as an upper boundary the time before the works of Bhāskara II (ca.1114-1183) started to have an impact (which has enabled us to include Sūryadeva Yājvan’s commentary, which dates from after Bhāskara II, but is ignorant of it) and after the vedic period, which had its own specific mathematical tradition or style. The period we are considering thus ranges thus from 499 AD to 1200 precisely.

Figure 1: Texts on mathematics in Sanskrit, VIIth-twelfth century



seems to have been, to a certain extent, and for certain authors, a sub-discipline of astronomy. A common conception of *gaṇita* in this context is “computational astronomy”. However, some Sanskrit authors of astronomical texts insisted that mathematics had an existence outside of astronomy¹⁶. This would explain why a certain number of procedures with no application in astronomy were stated in such chapters. Additionally, independent texts on mathematics, from the vedic time onwards, have been preserved. Accordingly, mathematical texts in an astronomical context, were different from autonomous mathematical texts. In the first and second part, these different texts will be collected together focussing on the fact that they concentrate on a same subject matter, which is given a specific name, *gaṇita*. In the third part, this difference will emerge again.

Table 1.1 gives a list of 15 texts. It includes two sets of texts. “Primary texts” : treatises and all the texts that stand alone; and “secondary texts”, those that need another to exist : commentaries. All the texts on mathematics known for this period are summarized graphically in Figure 1, stressing primary and secondary texts.

Texts so far identified as being commentaries, with *gaṇita* as subject matter, written during our chosen period¹⁷ and for which we have existing manuscripts are thus, in a chronological order:

- Bhāskara’s commentary on the second chapter of the *Āryabhaṭīya* (629 A. D.; hereafter abbreviated for the treatise into Ab and for the commentary into BAB, implicitly referring to chapter 2 when quoted in this way),

¹⁶See for instance (Keller, 2007), (Plofker, 2009).

¹⁷Commentaries on the treatises enumerated here have been written after our period but are not listed here. We will come back to this below.

- Pṛthudakṣvamin's mathematical commentary on the twelfth chapter of the *Brahmasphuṭasiddhānta* of Brahmagupta (the treatise is of 628 A. D. and the commentary of ca 864 A. D. ; hereafter abbreviated into BSS for the treatise and PBSS for the commentary, implicitly referring to chapter XII when quoted in this way),
- Someśvara's commentary on the second chapter of the *Āryabhaṭṭīya* (ca. 1040, hereafter abbreviated as SAB, implicitly referring to chapter 2),
- Sūryadeva Yajvan's mathematical commentary on the *Āryabhaṭṭīya* (Sūryadeva Yajvan is thought to have been born in 1191 A. D., his commentary is hereafter abbreviated into SYAB, implicitly referring to chapter 2).

To this we can maybe add:

- the anonymous and undated commentary on the *Pāṭīgaṇita* of Śrīdhara (fl. 850-950 A.D , date unknown for the commentary¹⁸; hereafter abbreviated into PG for the treatise and APG for the commentary.).

The following discussion will especially concentrate on the edited commentaries of this list: BAB, SYAB and APG.

Let us return to the texts these commentaries gloss.

The *Āryabhaṭṭīya* has been extensively commented upon.

Thus K. S. Shukla and K. V. Sarma count 19 commentators of the *Āryabhaṭṭīya*¹⁹, 12 of which are in Sanskrit. Half of them are from after the Xfifth century.

For Brahmagupta's BSS, on the other hand, two commentators are known. Furthermore, only seven manuscripts have been transmitted of this text. It concerns only one commentary, PBSS. Only two manuscripts, contain commentaries of Chapter XII. Four manuscripts out of the 34 remaining manuscripts of the BSS additionally provide an anonymous commentary on it²⁰.

Finally, as far as I know, PG is known through a unique manuscript, containing a similarly unique anonymous commentary on this text.

In other words, early treatises dealing with mathematics have not always come down to us with a great number of commentaries explaining them.

All primary texts evoked here have been entirely edited and translated into English. The Ab, BSS, BM, GSS, PG, L and BG have been edited and translated into English²¹. All other texts have been


¹⁸K. S. Shukla, who edited the text, considers that the commentary bears features of texts of the chosen time span. He especially draws similarities with the Bhakshālī Manuscript and the BSS. (K. S. Shukla, 1959, pp. xxviii-xxxiv).

¹⁹(K. V. Shukla & Sharma, 1976, p. xxv-lviii), we have included in this account, Prabhākara for which no extant commentary is known, although he is quoted by Bhāskara.

²⁰CESS IV 255 b; V 239 b.

²¹See (K. V. Shukla & Sharma, 1976), (M. S. Dvivedin, 1902), (Hayashi, 1995), (K. S. Shukla, 1959), (Rangacarya, 1912). There has been many printed editions of L and BG two texts, which are noted in CESS 4 308 a and 311 b; we can note the translation given in (Brahmagupta; Bhāskarācārya; Colebrooke, 1817).

Figure 2: Edited and translated texts on mathematics, fifth-twelfth century



edited²². The BSS is, for this period, the only non-extensively edited treatise containing a mathematical part. It is thus an exception: it has been but partially translated in English, in bits and pieces. Its special situation is probably due to the fact that no extant ancient commentaries in extant manuscripts are known for this text, part of which thus remains hard to understand.

Concerning commentaries, two (PBSS and BAB) have been partially translated into English²³, only one translated for its mathematical part (the BAB). A portion of SAB was edited with BAB.²⁴

The situation of these texts concerning editions and translations is given in Table 1.1, and Figure 2.

The case of BSS and PBSS set aside, notice that, strikingly, commentaries have been edited, but usually not translated.

²²The T was edited in (S. E. Dvivedin, 1899). The GT was edited with a later commentary (Kāpadīā, 1937). The MS was edited by Sudhākara Dvivedin in 1910 (S. Dvivedin, 1910), and partially translated into English by S. R. Sarma, (S. R. Sarma, 1966).

²³Part of PBSS’s astronomical commentary has been studied, edited and translated by Setsuro Ikeyama (Ikeyama, 2003). Pṛthudakṣvamin’s commentary on the twelfth chapter of the BSS, is found in a manuscript at the Indian Office and in what appears as a copy of this manuscript used by S. Dvivedi in Benares (CESS A. IV. 221 b), (Ikeyama, 2003, S5-S7). It has not been edited entirely, probably because the one recension is at times quite difficult to understand.

²⁴(K. S. Shukla, 1976).

Table 2: Editorial situation of texts on mathematics, in Sanskrit, fifth-twelfth century

Abbreviation	Treatise, Commentary, Others	Edited	Translated
Ab	Versified treatise	Yes	Yes
BSS	Versified treatise	Partly	Partly
BAB	Prose commentary	Yes	Partly
BM	Fragmentary text (versified rules and examples; prose resolutions)	Yes	Yes
PBSS	commentary	Partly	Partly
PG	Versified treatise	Yes	Yes
T	Treatise	Yes	No
GSS	Treatise	Yes	Yes
GT	Treatise	Yes	Partly (not the mathematical parts)
L	Treatise	Yes	Yes
BG	Treatise	Yes	Yes
[MS	Treatise	Yes	Partly]
SYAB	Commentary	Yes	No
[APG	Commentary	Yes	No]

This editorial situation can be taken as a symptom of the special treatment of commentaries as texts. It raises many questions: Were commentaries less translated because historians of science were not interested in them? Or was this a consequence of the state of manuscripts? These questions lead us to the way ancient collectors of texts, and maybe authors of commentaries themselves, thought of the text they were composing.

1.2 Reading and collecting commentaries on mathematical subjects

Who collected manuscripts? Who had them made? Who copied them? As C. Minkowski and D. Raina's articles in this volume underline, we have, to this date, only sporadic information enabling partial answers, varying from library to library, region to region, collection to collection. While restricting ourselves to our chosen corpus, information is especially sparse. We usually do not know the dates of manuscripts nor their stories, but it is reasonable to believe that they are mostly results of the copying frenzy of the late modern period described by C. Minkowski in his article of this volume.

In certain cases a great number of ancient hand made copies of a given text have been preserved. Thus the CESS counts for Ab ²⁵ 149 manuscripts of which 47 are with commentaries (more or less 1/3rd). These manuscripts can be found in 28 different libraries. They are mostly of unknown origin and are either paper or palm leaf.

Comparatively, extant manuscripts of commentaries are less important. Bhāskara's commentary is

²⁵CESS 1 51a-52b; 2 15b; 3 16a; 4 27b.

known through six manuscripts, five of which are in the same library in Kerala. They are all incomplete²⁶. Similarly Sūryadeva's commentary has been transmitted to us, through eight south Indian recensions and copies²⁷, while SAB is known through only one copy²⁸. The BSS is known through thirty-four manuscripts²⁹ and PBSS is known in seven manuscripts, two of which are fairly recent copy of two others, none of which are extant³⁰. Only two contain the commentary on chapter XII which is explicitly devoted to *gaṇita*³¹. Finally the edited PG is known through one manuscript the one containing APG³².

This is summarized in Table 3.

Table 3: Number of manuscripts for commentaries and treatises on mathematics, fifth-twelfth century

Text	Treatise	Commentary	Number of remaining manuscripts
Ab	x		47
BAB		x	6
SAB		x	1
BSS	x		24
PBSS		x	7
PG	x		1
APG		x	1

Therefore, in these collections, commentaries were much less numerous than treatises, and not always complete. Is this due to the hazards of preservation? Does it reflect a trend in the conception of commentaries when the texts were copied or collected sometime during the eighteenth or nineteenth century? Did the authors of commentaries themselves think of their commentaries as fragmentary texts? Does this explain the way commentaries were subsequently treated in the historiography? To answer these questions with precision, we need to delve a bit more into the complexity of each text, and how it has been transmitted to us.

Before looking at how these commentaries were transmitted, let us specify what kind of texts this analysis is concerned with.

1.3 A first rough characterization of commentaries on mathematics

There is something tricky in attempting to individualize mathematical commentaries among other texts on mathematics in Sanskrit, since the aim of this article is precisely to underline that much stills needs to be done.

²⁶(K. S. Shukla, 1976), CESS IV 297b.

²⁷(K. V. Sarma, 1976, p. xvii to xxv).

²⁸(Sen et al., 1966, p. 202), CESS I-II 51a.

²⁹CESS IV 254 b-255b, CESS V 239 b- 240 a.

³⁰CESS IV 221 a, CESS V 224 a .

³¹(Ikeyama, 2003, p. S7).

³²(K. S. Shukla, 1959). As noted previously (Sen et al., 1966, p. 204) note a second incomplete manuscript of the PG *tīkā* in the Descriptive catalogue of the Oriental Mss in the Mackenzie Collection, compiled by H. H . Wilson in Madras in 1882, which would be in fifty four-folios.

Titles of texts, and expressions used in them, testifies that the Sanskrit scholarly tradition distinguished between treatises (*śāstra*, *tantra*, *siddhānta*) and commentaries (*vyākhyā*, *bhāṣya*, *ṭīkā*)³³. This was also the case in the field of *jyotiṣa* and *gaṇita*³⁴. All sorts of other kinds of texts were composed in this field such as handbooks for making calendars (*karāṇa*), almanacs (*pañcāṅga*), compendiums (*nibandha*), etc³⁵. With this diversity in mind, we can thus wonder if certain kinds of text were preferred to others in the past. Did such preferences vary over time, in different places, according to certain sub-fields? Does this tell us something of the conception different actors had of what an astronomical or mathematical text was to be? Of how such disciplines were practiced? Did historians of science, discovering these texts, focus on one kind of text over another?

Concerning texts of the fifth-twelfth century, the Ab is referred to as a *tantra* by Bhāskara³⁶ and as a *śāstra* by Sūryadeva Yajvan. APG refers to the text it comments as a *śāstra*³⁷.

Similarly a dirth of names are used by authors to evoke the commentaries they are writing. Thus, Bhāskara calls his commentary a *vyākhyā*³⁸. The tradition, as reflected in the title given to his commentary, evokes however a *bhāṣya*. Sūryadeva Yajvan from time to time refers to his own text as a *vyākhyā*, and, more commonly, as a *prakāśa*, “light”³⁹. The APG calls itself a *ṭīkā*⁴⁰.

We do not know then if these names are just synonyms or if they tell us something of the kind of commentary, authors and readers had in mind, when they read or gave them such names.

A commentary, by definition, is a secondary text, a deuteronomic text, a text that needs another to exist⁴¹. Is this definition however sufficient to characterize it as a text? Sanskrit commentaries are very

³³An attempt at characterizing “scholastic sanskrit” of commentaries (in the case of grammatical, philosophical and logical texts) is given in (Tubb, 2007).

³⁴Concerning commentaries, many different technical names are recorded either in the titles or by D. Pingree in the CESS. Keeping in mind that the numbers should be subject to much caution, preeminently *ṭīkās* (549- 67,2% of all commentaries), but also *vyākhyās* (85-10,4%), *vivṛttis* (50-6,1%) and *bhāṣyas* (34-4,1%) among *avacūrṇis*, *vārtikkas*, *tippanaṇis*, *vivāraṇa*’s are noted. This diversity raises the general question of how titles were given to texts. We seldom encounter here the names of patrons, as in the cases examined by C. Minkowski. Were titles given by authors or by later scholars? Where titles modified by those who copied texts? This set of questions can be extended to all the texts of the census. I have counted only 205 (5,5%) texts bearing *siddhānta* in their title. I count 18 *śāstras* and *tantras*. Titles can express either that they bestow knowledge 141 (*saṅgraha*, *jñāna*; 3, 8 %) or the idea of providing an essence of something 118 (*phala*, *sāra*; 3,2%); sometimes both (*sārasaṅgraha* being quite a common title compound). The metaphor of light (*dīpika*, *prakāśa*) is used also (289; 7,8%), for commentaries also (28).

³⁵(Pingree, 1981). I have counted in the CESS 130 (3,5 %) texts bearing the name *karāṇa* or associated titles and 66 (1,7%) almanacs (*pañcāṅgas*) and texts explaining how to make them. The CESS notes a number of non-standard texts, such as the *Aparājītapṛcchā* of Bhuvanadeva (fl. twelfth century) whose text on architecture is written in dialogue (CESS V 264 a.).

³⁶To be more specific, it is the three last chapters of the *Āryabhaṭṭīya* which are referred to in this way, when concluding the commentaries to each of these chapters. (K. V. Sarma, 1976, p. xxv), (K. S. Shukla, 1976, p. 171; p. 239; p. 288).

³⁷(K. S. Shukla, 1959, p.1).


³⁸See the *maṅgalācaraṇam* of BAB.2 : *vyākhyānaṃ gurupādalabdham adhunā kiñcin mayā likhyate*, (K. S. Shukla, 1976, p. 43).

³⁹Thus as the end of the introduction which begins his commentary he writes *evam upodghātaṃ pradarsya śāstraṃ vyākhyāyate*. (K. V. Sarma, 1976, p. 7) At the end of that chapter’s commentary, he refers to his text as a *prakāśa*. (K. V. Sarma, 1976, p. 32, p. 79 (note 11); p. 117, p. 185). The end of SYAB.2 uses also again the verbal root *vyāksh-*.

⁴⁰(K. S. Shukla, 1959, p.1).

⁴¹On the question of “secondary texts” in the history of mathematics, see (Netz, 1998), (Chemla, 1999), (Bernard, 2003)

Figure 3: Palm leaf manuscript of BAB in a copy of the Kerala University Oriental Manuscripts Library



diverse. This is somewhat reflected in the mathematical field. Some commentaries respect the original order of the text, when others do not⁴². Thus BAB, SAB, SYAB and APG⁴³ respect the order of the text whereas PBSS does not⁴⁴. SYAB develops a long introduction (*upodghata*) before the gloss of the text, this is not the case in the other commentaries considered here. So that if all commentaries have in common the fact that they comment a text, the way they do comment is quite variable. The relation between a commentary and the treatise it comments needs to be specified.

All commentaries considered here quote entirely the text they comment⁴⁵. Nonetheless, finding a stylistic criteria separating treatises from commentaries is a difficult task. As soon as a principle of separation is brought up, a counter-example can be provided almost immediately.

For instance, manuscripts, did not always graphically distinguish treatises from their commentaries. Thus, as illustrated in Figure 3, the treatises seems to be an undifferentiated part of the commentary. In some cases, such as in Figure 4, the commented part was colored or graphically disposed separately from the treatise, but this was not a systematical rule⁴⁶. Therefore, even thought titles suggest a difference, the material culture does not always follow it. Does this mean that copied texts were not made to be read? A historical study of traditions of reading and copying in the Indian subcontinent could shed a much needed light⁴⁷.

and also Chemla in this volume.

⁴²See (Bronkhorst, 1990).

⁴³One should recall however that PG as given in Shukla's edition is known in this unique recension only (K. S. Shukla, 1959).


⁴⁴According to CESS IV 221b the order is, for chapters noted in roman numbers: I 1-3; XXI 1-XXII 3; I 4-II 68; XV 1-9; III 1-XIV 55; XV 1à-XX 19; and XXII 4-XXIV 13. The question being then, what is the logic found by PBSS for this order.

⁴⁵However, they all quote also other texts, although not completely. Thus SYAB quotes often PG, and APG, BSS. SYAB often paraphrases BAB. Therefore, commentaries are composite texts made of parts of previously composed texts, that are sometimes rewritten (paraphrase), intertwined with their own original compositions. The versified examples commentaries share with each other can be seen as a form of quotation as well.

⁴⁶One can wonder if this does not spring from a modern (eighteenth-nineteenth century) scribal tradition which may very well have been influenced by the new presence of European texts, or as suggested in (Plofker, 2009, A.3, 305) an islamic one.

⁴⁷Note also that a strong stylistic criteria seperating commentaries from treatises could help philologists to determine,

Figure 4: Paper manuscript with colored highlights of MS in a copy of the Mumbai University Library



The opposition of treatises and commentaries has often been described as the written reflection of the opposition, in an oral tradition, of what was to be known by heart (the treatise) and the explanations that were given subsequently (the commentary). The treatise being an oral composition, the commentary a written text⁴⁸. This is rooted in what commentators write. Thus Bhāskara insists on an opposition between Āryabhaṭa who states orally (*āh-*) the commented treatise, and Bhāskara’s own writing, (*likh-*). However, Hayashi has shown that the word *likh-* (to write) is used as a synonym for *vac-* (to speak) in the BM⁴⁹. In this case, there appears to be no difference between a written text and an oral one.

Even the opposition between versified and prose text does not always hold its way. Indeed, treatises here are all versified. Thus chapter 2 of the AB, chapter XII of the BSS and the PG are composed in *ārya* verses. The commentaries all include prose sections, which can present a great diversity : they can set up dialogs for instance, or grammatical analysis. But all include versified parts. Thus BAB contains versified tables. All commentaries contain versified examples⁵⁰.

The existence of solved examples may be a unique feature of mathematical commentaries in Sanskrit, together with the fact that they contain non discursive parts, such as numerical tables and drawings. Only further systematic study of the characteristics of Sanskrit commentaries, especially of Sanskrit commentaries in the field of *jyotiṣa*, may provide additional elements.

What characterises commentaries and treatises appears as a complex and difficult question, when considered in a general case as much as when restricting ourselves to the case of commentaries whose topic is mathematics⁵¹;

Internal evidence may tell us something then of how texts were conceived in relation to one another. Questioning why and how texts were copied, with what aim may also yield some evidence of a different kind, providing elements for a historical evolution in conceptions of such texts. The history of text while editing manuscripts, what belongs to one and the other.

⁴⁸See for instance (K. S. Shukla, 1976, Introduction).

⁴⁹(Hayashi, 1995, p. 85).

⁵⁰In his edition of PG and APG, Shukla seems to hesitate: are the examples part of the treatise, or part of the commentary? Editions of L, all consider examples as part of the treatise.

⁵¹(Plofker, 2009) evokes in different parts of her book certain rough characteristics of mathematical commentaries: their uses of proofs and language games essentially.

copying, collection and reading can additionally give us contextual information on who had them collected and copied, as we will now see.

1.4 An example: manuscripts of SYAB

K. V. Sarma has given a description of the codex- that is the bundle in which sometimes several texts are collected within a library, indicating that they have either been copied together or had been collected at the time they were integrated in the library- in which the SYAB is found in Kerala⁵². It first includes a set of manuscripts part of a collection made by scholarly astronomers.

Indeed, the codex containing Manuscript A, Codex C. 224-A , was made for the royal family of Eḍappaḷī of Kerala, in 1753. It included, the *Bhaṭaparakāśikā* of Sūryadeva Yajvan (SYAB) and also the *Laghubhāskarīya* and *Mahābhāskarīya* of Bhāskara I (seventh century), the *Tantrasaṅgraha* of Nīlakaṇṭha Somayājīn (fl. 1450), the *Sūryasiddhānta* (tenth century), the *Goladīpikā* of Parameśvara (fourteenth) and the *Siddhāntaśekhara* of Śrīpati (fl. 1050). All these texts have in common their subject matter: astronomy. Similarly manuscript D, also originating from a codex (C. 22475-A) belonging to the same royal family of Kerala, contains both SYAB and the first chapter of Ab, alone.

Manuscript E of the same edition belongs to a codex (C.2121 C and D) which originally came from the “library of a family of astronomical scholars, the Maṅgalappaḷī Illam, at Āranmuḷa, in southern Kerala”⁵³. The codex contains with SYAB, the 3 last chapters of the Ab, T and also the *Mahābhāskarīya* of Bhāskara I, a *Mahābhāskarīyavyakhyā* (an anonymous commentary on the *Mahābhāskarīya*), the *Laghumānasakaraṇa* of Muñjāla (fl. 932) with an anonymous commentary, a commentary on chapter II and parts of chapter III of the *Sūryasiddhānta*, the whole of the *Sūryasiddhānta*, and an anonymous prose *Rāmāyaṇa*. Setting aside the prose version of the famous Indian Epic, once again such a codex concentrates essentially on astronomical and mathematical lore. Here, only part of a commentary on the *Sūryasiddhānta* is copied, while the treatise itself is extensively copied, separately. Ab, similarly, is known to have been transmitted in two separate parts, the first chapter being copied separately (as in the codex for Manuscript A) from the 3 other parts (as in the codex of Manuscript E).

Commentaries then were not copied together with other commentaries, but a codex could contain a treatise alone, and a commentary of a couple of chapters by a given author. Unlike the Chinese tradition, texts of important treatises could be copied and collected without any commentaries. Different commentaries of a same text were usually copied separately, one did not record in the same manuscript different commentaries of a same verse, as for the Chinese *Nine Chapters*.

Another codex, shows us a text copied for another kind of context: that of a brahmin cast of Kerala, the *nampūtīri*, whose priests follow vedic rituals (*śrauta*). The codex which contains SYAB, C. 2320-A, contains also a text describing the horse sacrifice and detailed accounts of expenses for a ceremony carried out in 1535. The codex seems a copy of a manuscript dating from 1536. Indeed, Sūryadeva understood Āryabhaṭa’s text in relation to *śrauta*, being himself a performer of such rituals⁵⁴. This small codex is

⁵²(K. V. Sarma, 1976, Introduction, xvii-xx).

⁵³(K. V. Sarma, 1976, Introduction, xix)

⁵⁴SYAB peculiarly states this clearly in its general introduction to Ab (K. V. Sarma, 1976, xxv-xxvi, 2-4). Indeed,

of the kind of *śrauta* collection C. Minkowski describes for the Toro family, although the copy of this *siddhāntic* text, may seem surprising. Was the use of *siddhāntic* astronomy by ritualist families a usual phenomena?

On the contrary, Manuscript B of Sarma's edition was given by a scholarly family coming from the *vattapalli maṭham* (e.g. a religious complex) near the southernmost tip of the Indian sub-continent, *kanyākumārī*, in Tamil Nadu. With the *Bhaṭṭaparakāśikā* (SYAB) the codex contains an *Āṣṭādhyāyī-sūtrānukramaṇi*, eg an alphabetical index of Pāṇini's *sūtras*, in other words a text of grammatical lore⁵⁵.

In this case, SYAB seems to have been copied as part of a more general endeavor to collect general Sanskrit scholarship.

The provenance of manuscripts, then, underlines an already well known posterity of *Āryabhaṭa* in Kerala. SYAB seems to have been used in three different, although probably not separate, social contexts: that of scholarly astronomers, that of priests performing vedic rituals, the more general scholarly atmosphere of south Indians monasteries.

We have however but little information on how these texts were integrated into the Kerala University Oriental Manuscript Library were they are now to be found. The library was originally created by the government of Travencore (one of the autonomous states within the British Raj) in 1908, aiming at the preservation of their own heritage⁵⁶. More on the history of this library needs to be investigated, but the structure of the codex in which SYAB is to be found recalls the kind of collection work C. Minkowski described.

Not all manuscripts of other mathematical texts provide informations as rich as those of SYAB. The BAB manuscripts preserved at the KUOML are not given within a codex, for instance. Similarly, existing manuscripts of the PBSS tell us more of their recent collecting, then how tradition has transmitted them. Thus, the two manuscripts which explicitly contain chapter XII of the PBSS, are those that served respectively for the translation Colebrooke made of this text and the edition that S. Dvivedin made in Benares⁵⁷.

Treatises on mathematics then have been more often studied and translated than commentaries on mathematics, although mathematics as a discipline has attracted far more scholarship in the last two centuries than other parts of *jyotiṣa* lore. Tools to differentiate and understand how commentaries and treatises relate to each other, when each individual text seems to have an individual story of preservation/transmission have been difficult to find. In the early modern period in South India, royal families with a marked interest in astronomy, ritualist families and religious groupings had copies made of texts on mathematics. Those who copied commentaries in south India in the early modern period, seemed to *Āryabhaṭa* himself can hardly be thought of as a ritualist, famous as he is for the distance his treatise took with puranic cosmology.

⁵⁵(K. V. Sarma, 1976, xviii).

⁵⁶The "index of manuscripts" of the library notes that "In 1940 it possessed 3000 manuscripts, 142 publications in sanskrit, 63 in Malayalam. Travancore University (which became the University of Kerala) organized after its establishment (1938) a manuscript preservation and collection department. Both were amalgamated (sic) in 1940. In 1958 there was 28 000 Codices in Sanskrit; 5 000 in Malayalam."

⁵⁷See (Pingree, 1970-1995, op.cit), (Ikeyama, 2003, op.cit) and (M. S. Dvivedin, 1902).

have considered them not as extant texts.

Did authors consider commentaries as whole texts? Were treatises also considered as such? One may also wonder how much the attitude of early modern copiers was subsequently reflected by the Europeans who read the texts at the end of the eighteenth century and the beginning of the nineteenth century.

2 Rediscovering Ab, BSS, PG and their commentaries in the historiography of Indian mathematics

A first attempt at highlighting textual aspects of the historiography of mathematics in India will now be undertaken. How did historians of mathematics look at the Ab, the BSS and the PG and their seventh-twelfth century commentaries? No simple trend can be found unifying how different historians dealt with commentaries. The key may be whether historians were mathematicians or philologists. The more the historian was a mathematician, the less there seems to have been a sensitivity to text, the more he was a philologist, the more the commentary was given an important place. However, this does not mean that commentaries were always seen as secondary texts by mathematicians and important texts by philologists. As the twentieth century came to a close, the general historiographical trend has been to pay more and more attention to the mathematical contents of commentaries. We cannot afford here to look closely at the shifting attitudes of all different actors, but we will try to draw out some of the characteristics of Colebrooke, Datta & Sing and K. S. Shukla's attitude towards commentaries.

As early as the seventeenth century a certain number of people in Europe knew of the existence of Sanskrit astronomical treatises, by the testimonies of travelers, academic envoys and jesuit missionaries, as D. Raina's article in this volume explains⁵⁸. It took time for Europeans curious of them, to get hold of the texts and be able to study them. By the early nineteenth century, the first translations of Sanskrit texts on mathematics in European languages (especially English) were made. Thus in 1812, in London, Stratchey translated for the first time the BG in English, in 1816 Taylor translated the BG in Mumbai, followed by Colebrooke's translation of L and BG together with the mathematical chapters of Brahmagupta's BSS which was published in London in 1817⁵⁹.

2.1 Colebrooke and commentaries

Colebrooke's publication proved to be a landmark. He was the first serious well established indologist interested in mathematical texts from the Indian subcontinent. He was at the time a former director of the Asiatic Society of Bengal, a recognized specialist of Hindu Law, Vedic ritual and Indian languages.

His translations of these mathematical texts was preceded by a general "dissertation", followed by "notes and illustrations", aiming at placing these texts in a general history of mathematics which would provide for India a name it had until then lacked⁶⁰. His introduction takes a strong position on the antiquity of the Indian tradition in mathematics, especially in algebra, in an ongoing controversy which

⁵⁸See also (Raina, 2003), (Raina, 1999).

⁵⁹(Brahmagupta; Bhāskarācārya; Colebrooke, 1817).

⁶⁰*Op.cit.*; p. xvi.

it will heighten⁶¹. The quality of his translations, generally made in close collaboration with pandits, has made it an enduring reference.

Colebrooke included portions of commentaries his translations' footnotes. Thus Gaṅgadhāra (fl. 1420), Sūryadasa (1541), Gaṇeṣa's (fl.1520/1554) and also Ramakṛṣṇa's (? date unknown maybe 1687⁶²) commentaries are partially included in L⁶³'s translation; Kṛṣṇa's (ca.1615), Rangunāṭha's (?) and Ramakṛṣṇa's commentaries are used in BG's translation. Finally, PBSS (noted as "CA", an abbreviation of *Caturdeva*, a part of his name) is used (and quoted) to translate the BSS. Furthermore, although the original text is not known to him or to his English readers, Colebrooke's introduction refers and discusses Āryabhaṭa's works⁶⁴. Āryabhaṭa was indeed criticized by Brahmagupta; his verses were discussed and quoted by diverse commentators. Colebrooke also refers to a work of Śrīdhara, which is not however our PG⁶⁵. Thus Colebrooke's readers came to know of Āryabhaṭa, Brahmagupta and Śrīdhara.

Colebrooke aimed at describing the mathematical tradition of India. This led him to consider only the mathematical part of Brahmagupta's treatise, the BSS. And consequently only a portion of PBSS. By doing so, was he prolonging an attested tradition of copying (and thus showing a separate interest) of mathematical chapters of astronomical treatise that existed in the Sanskrit tradition? This selection of BSS's chapters in a printed edition, may also mark the beginning of a long enduring historiographical trend noted in the introduction: mathematical subjects have been more treated than astronomy or astrology in the study of old *jyotiṣa* texts.

In Colebrooke's introduction, commentators first appear as proofs of the authenticity and antiquity of the texts he is concerned with. He writes⁶⁶:

“The genuineness of the text is established with no less certainty [than its date] by numerous commentaries in Sanskrit, besides a Persian version of it. Those commentaries comprise a perpetual gloss, in which every passage of the original is noticed and interpreted : and every word of it is repeated and explained, a comparison of them authenticates the text where they agree; and would serve, where they did not, to detect any alterations of it that might have taken place, or variations, if any had crept in, subsequent to the composition of the earliest of them. A careful collation of several commentaries, and of three copies of the original work, has been made, and it will be seen in the notes to the translation how unimportant are the discrepancies. ”

Commentaries are thus useful and necessary when one wants to edit a text, they are philological tools. However the way they are integrated in Colebrooke's translations, pin points to the fact that commentaries were far from being just that. They were used to understand the treatises. They were stimulating mathematically with their examples and proofs. However, a commentary was not treated as a text in itself. It was given in bits and pieces. Selected.

Look at the translation, as seen in Figure 5. The commentary appears typographically as a secondary

⁶¹(Kejariwal, 1988, 111-112).

⁶²CESS V 453 a.

⁶³*Op.cit.* Note A p. xxv and p.xxvii

⁶⁴*Op.cit.* Introduction, sections G to I pp. xxxvii-xiv.

⁶⁵*Op.cit.* p.v he writes that he has a copy of “Sridhara's compendium of arithmetic”, which is probably the *Triśatika*.

⁶⁶(Brahmagupta; Bhāskarācārya; Colebrooke, 1817, iii)

text, written in a smaller font. It is fragmentary, given in different footnotes. However, it literally spills over and eats the space which is meant for the treatise. The commentary's importance for Colebrooke is visually explicit.

Recalling that codex's sometimes include only portions of commentaries, we may wonder how much this attitude, consisting in considering commentaries in bits and pieces, reflects the way pandits that trained Colebrooke, and then perhaps helped him in collating and understanding the texts, worked. A history of how commentaries were thought of and read in the Indian subcontinent would be very helpful here. A precise description of how Colebrooke (and other European scholars) worked with pandits in relation to texts would be useful as well⁶⁷.

2.2 An Indian scholarship with commentaries: Datta & Singh and K. S. Shukla

During the nineteenth century, the history of mathematics in India slowly opened officially to Indian scholars, who elaborate a scholarship that is as much directed towards an inner audience, as an answer and a discussion with European interlocutors⁶⁸. Their presence is first seen in articles discussing authorship of texts, before being felt in a series of editions and translations of texts on mathematics. Thus, the names of Datta, Sengupta and Dvivedin appear in an initial period of confusion where the fifth century Āryabhaṭa was confused with his eleventh century namesake, and the seventh century Bhāskara I was confused with his twelfth century namesake.

By the end of the nineteenth century the movement, which started at the beginning of the century, of edition, translation and analysis of texts on mathematics in Sanskrit comes to a peak. Kern in 1874⁶⁹ edits for the first time⁷⁰ the Ab. His edition is printed with Parameśvara (fourteenth century) 's commentary. His introduction evokes SYAB, which is quoted and referred to by Parameśvara; but not BAB. In 1879, chapter 2 of the Ab is translated and analyzed into French by Leon Rodet⁷¹. In 1896, Dikshit gives an edition of the BSS with his own commentary⁷². These editions are followed by a number of translations in English and the first studies in this language. Thus in 1907 and 1908 G. R. Kaye publishes his controversial *Notes on Indian Mathematics*, part two of which is devoted to Āryabhaṭa⁷³. Sengupta publishes a first English translation of the Ab⁷⁴, followed by Clark in 1930⁷⁵. B. Datta and S. N. Singh publish in 1937 the enduring classic "Hindu Mathematics"⁷⁶. Their main aim is to provide a general description of all different ways Hindu mathematicians practiced elementary and

⁶⁷The latter has been studied partially in (Kejariwal, 1988), (Aklujkar, 2001), (Bayly, 1996) and others, but little seems to have survived on how precisely pandits and Colebrooke worked texts out.

⁶⁸(Keller, 2006b).

⁶⁹(Kern, 1874).

⁷⁰The tradition of copying manuscripts can of course also be seen as an editorial tradition of classical India, but we printed books are referred to here.

⁷¹(Rodet, 1879)

⁷²(Dikshit, 1896).


⁷³(Kaye, March 1908).

⁷⁴(Sengupta, 1927).

⁷⁵(Clark, 1930).

⁷⁶(Datta, 1935).

Figure 5: The BSS and PBSS in Colebrooke's translation



GANITADHYAYA, ON ARITHMETIC;

THE TWELFTH CHAPTER OF THE

BRAHME-SPHUTA-SIDDHANTA,

BY **BRAHMEGUPTA;**

WITH SELECTIONS FROM THE COMMENTARY ENTITLED

VASANA-BHASHYA,

BY **CHATURVEDA-PRITHUDACA-SWAMI.**

CHAPTER XII.

ARITHMETIC.

SECTION I.

1. He, who distinctly and severally knows addition and the rest of the twenty logistics, and the eight determinations including measurement by shadow,¹ is a mathematician.²

2. Quantities, as well numerators as denominators, being multiplied by

¹ Addition, subtraction, multiplication, division, square, square-root, cube, cube-root, five [should be, six] rules of reduction of fractions, rule of three terms [direct and inverse,] of five terms, seven terms, nine terms, eleven terms, and barter, are twenty (*parikramā*) arithmetical operations. Mixture, progression, plane figure, excavation, stack, saw, mound, and shadow, are eight determinations (*tyuktakāra*).
Ch.

² For topics of Algebra, see note on § 66.

³ *Gaṇaka*, a calculator; a proficient competent to the study of the sphere.
Ch.

the opposite denominator, are reduced to a common denomination. In addition, the numerators are to be united.¹ In subtraction, their difference is to be taken.²

3. Integers are multiplied by the denominators and have the numerators added. The product of the numerators, divided by the product of the denominators, is multiplication³ of two or of many terms.⁴

4. Both terms being rendered homogeneous,⁵ the denominator and nu-

¹ SCANDA-SĒK-ĀCHĀRYA, who has exhibited addition by a rule for the summation of series of the arithmetics, has done so to show the figure of sums; and he has separately treated of figurate quantity (*cahātra-rāhī*), to show the area of such figure in an oblong. But, in this work, addition being the subject, sum is taught; and the author will teach its figure by a rule for the summation of series (§ 19). In this place, however, sum and difference of quantities having like denominators are shown: and that is fit.
Ch.

² Example of addition:—What is the sum of one and a third, one and a half, one and a sixth part, and the integer three, added together?

Statement: $1\frac{1}{3} 1\frac{1}{2} 1\frac{1}{6} 3$. Or reduced $\frac{4}{3} \frac{3}{2} \frac{2}{6} 3$.

The numerator and denominator of the first term being multiplied by the denominator of the second, 2, and those of the second by that of the first, 3, they are reduced to the same denominator ($\frac{8}{6}$; and, uniting the numerators, $\frac{11}{6}$). With the third term no such operation can be, since the denominator is the same: union of the numerators is alone to be made; $\frac{11}{6} + \frac{2}{6}$, which abridged is $2\frac{1}{6}$. So with the fourth term: and the addition being completed, the sum is 7.

Subtraction is to be performed in a similar manner; and the converse of the same example may serve.
Ch.

³ *Pratyuppanna*, product of two proposed quantities.—Ch. See a rule of long multiplication, § 55.

⁴ Example: Say quickly what is the area of an oblong, in which the side is ten and a half, and the upright seventy sixths.

Statement: $10\frac{1}{2} 11\frac{1}{6}$. Multiplying the integers by the denominators, adding the numerators, and abridging, the two quantities become $\frac{75}{6}$ and $\frac{11}{6}$. From the product of the numerators 755, divided by the product of the denominators 6, the quotient obtained is $122\frac{1}{6}$. It is the area of the oblong.

Others here exhibit an example of the rule of three terms, making unity stand for the argument or first term. For instance, if one *pala* of pepper be bought for six and a half *panas*, what is the price of twenty-six *panas*? Answer: 169 *panas*.
Ch.

⁵ The method of rendering homogeneous has been delivered in the foregoing rule (§ 3) "Integers are multiplied by the denominators," &c.—Ch. It is reduction to the form of an improper fraction.

⁶ It is not quite clear whether the examples are the author's or the commentator's. The metre of them is different from that of the rules; and they are not comprehended, either in this or in the chapter on Algebra, in the summed contents at the close of each. They are probably the commentator's; and consigned therefore to the notes.

sometimes higher mathematics, each author adding a stone to this description. But they also want to answer G. R. Kaye's claims on the Arabic or European origin of Indian mathematics in general and Ab's mathematics in particular. To do so, part of their effort consists in comparing the history of mathematics in Europe with what has been discovered about the history of mathematics in the Indian subcontinent. Datta & Singh write then, to a certain extent, a history of mathematics in India with its great authors and treatises. As trained mathematicians, their focus is essentially on the mathematical contents of the texts⁷⁷. B. Datta and A. N. Singh consider mathematical commentaries essentially as mathematical texts. Thus Bhāskara I, whose text was known but was not published, is referred to several times as an astronomer sometimes dealing with mathematics⁷⁸. His commentary is at times quoted to explain or give an interpretation of Ab's verses⁷⁹, sometimes even in footnotes like in Colebrooke's text⁸⁰, often together with other commentators of Ab such as Nīlakaṇṭha (fourteenth century), none of whose commentaries were at the time edited texts. Essentially, however, BAB is referred to for its mathematical contents, outside of its relation with Ab⁸¹. It is mingled at times with the contents of Bhāskara's other astronomical texts⁸².

With the independence and the creation of institutions for the history of science in India, a new wave of editions is set forth. K. S. Shukla was an important actor of this movement. In 1959, he publishes, at the University of Lucknow, an edition of PG with APG, together with an English translation of PG⁸³. He then turns to Bhāskara's work, first editing and translating his treatises, which can be seen as elaborations of Āryabhaṭa's astronomy, the *Laghubhāskarīya* and the *Mahābhāskarīya*⁸⁴. In 1976, an edition and translation of the AB, with editions of BAB and SYAB within the Indian National Science Academy are conjointly published by K. S. Shukla and S. R. Sharma⁸⁵.

By the 80's a new generation will take up the study of commentaries with mathematical subjects. On the one hand, publications on the Mādhava school of mathematics will call the attention of historians of mathematics on scholiasts of Āryabhaṭa; on the other hand Japanese students of D. Pingree, T. Hayashi in particular, will start publishing articles on the mathematical contents of different commentaries on Ab, BG and L. We can add to this enumeration the publications of F. Patte's PhD and my own, to testify of the growing interest for mathematical commentaries in Sanskrit as the twentieth century came to an end⁸⁶.

⁷⁷But they also embody a dying tradition of mastering Sanskrit texts on *jyotiṣa*. After all, B. Datta was at the end of his life addressed as *pandit*. Furthermore the enduring quality of their translations attest this mastering. "Hindu Mathematics" is certainly a blend of the two traditions, *jyotiṣa* lore and modern historiography of mathematics. A detailed scrutiny of Datta & Singh's works could probably yield much information on the first.

⁷⁸(Datta, 1935, Volume I, 125).

⁷⁹(Datta, 1935, Volume I, 66-67; 196; 211. Volume II, 93-95).

⁸⁰(Datta, 1935, Volume I, 170). SYAB also such as in *op. cit.*[Volume II, 91, footnote 4].

⁸¹(Datta, 1935, Volume I, 80, 82, 87, 130, 204, 239; Volume II, 87, 238).

⁸²Thus the entire part devoted to the *kuṭṭaka* in Volume 2, quotes all the different texts of Bhāskara I, sometimes to present his own algorithms, some other times as explaining Ab's algorithm.

⁸³(K. S. Shukla, 1959).

⁸⁴(K. S. Shukla, 1963), (K. S. Shukla, 1960)

⁸⁵(K. V. Shukla & Sharma, 1976), (K. S. Shukla, 1976), (K. V. Sarma, 1976).

⁸⁶How much have these attitudes towards commentaries been linked to more general developments in the field of Indology? Indeed, Indology developed a special focus on the study of treatises and the contents of important commentaries, somewhat

Shukla's editions uses commentaries in three separate ways: commentaries are first used, as in Colebrooke's case, as a philological assessment of the original text he wants to edit. They are also used to explain the text. Thus APG is not translated but Shukla refers to it, in the written comments that escort his translation of PG. Shukla sometimes seems to consider commentators as giving a peculiar interpretation of the treatise, and at other times as explicating the contents. In his co-edition and translation of the Ab, commentators are summoned to add a mathematical depth to algorithms. They are at times quoted for their conflicting interpretations. Finally in some instances, especially concerning BAB, commentaries appear as a mathematical text in their own right⁸⁷. The trend that sees commentaries not only as philological aids, but also as independent mathematical texts, has been growing. This has no doubt to do with a general trend in the history of mathematics at large, as such approaches seem to have been characteristic of the Chinese corpus as well.

Commentaries then were used, read and analyzed but seldom translated by modern historians of mathematics. This made quite sense when commentaries were thought of, as often they were, as philological tools to edit and understand the texts they commented. However, the lack of translation remains quite surprising when commentaries are considered as texts on mathematics in their own right. Furthermore, if commentaries and treatises are seen as ballroom dancing couples, it is as if the focus had been essentially on the treatise without its partner, sometimes on the commentary without its partner, and sometimes on details of how their steps follow each other. However, the global picture of how they dance together has not been drawn, or even aimed at.

3 Relating commentaries to their treatises: the example of square root extractions

In studies on the history of mathematics in India, the mathematical relation of commentaries to the text they comment has been left, in general, unresolved. Reflections on the relation of one text to another one, usually restricted to the grid of a "right or wrong" interpretation of the treatise by the commentary. Scholarship on the mathematical contents of commentaries, has focussed on the interesting mathematical ideas they contained, and thus essentially their proofs⁸⁸. Implicitly then a relation of the commentary as providing mathematical justifications of treatise is drawn. We would like to show that the relation is more complex.

neglecting to reflect on the commentary as a specific kind of text. The last five, ten years has seen however a renewed interest in this kind of texts, as testified by the conference "forms and uses of the commentary in the Indian world", which was held in Pondicherry in february 2005, see <http://www.ifpindia.org/Forms-and-Uses-of-the-Commentary-in-the-Indian-World.html>, or the already noted publication of (Tubb, 2007).

⁸⁷Before publishing his edition of BAB, Shukla published a number of analysis, pinpointing the mathematical importance of the text. (K. S. Shukla, 1972)

⁸⁸(Srinivas, 1990), (Patte, 2004), (Plofker, 2009). Strangely enough little reflection has been published on comments concerned with defining the field of *ganīta*. Such reflections could however explain why chapters on *ganīta* containing algorithms with little astronomical applications, were included in treatises on astronomy. See (Pingree, 1981), (Keller, 2007), (Plofker, 2009).

In the following, rules to extract square roots, which are found in Ab and PG, but not in BSS, will be examined.

3.1 Extracting square roots along different lines

The square root extraction procedures during this period use the decimal place-value notation as a basis. The algorithms given by our authors are not “useful” procedures to extract square roots, such as the interpolations usually described in astronomical (parts of) treatises. They all suppose that one extracts the root of a perfect square⁸⁹. The idea is to recognize in a number written with the decimal place-value notation the hidden development of a square expansion. To say it in other words, this would mean to recognize in a number written as $a_{2n} \times 10^{2n} + a_{2n-1} \times 10^{2n-1} + \dots + a_1 \times 10^2 + a_0 \times 10 + c^2$ the development of a square of the kind $(b_n \times 10^n + \dots + b_i \times 10^i + \dots + c)^2$ ($i < n$). Crucial then to this algorithm is to distinguish between powers of ten that are also squares (the even powers of ten), and those that are not.⁹⁰

Let us note that Ab’s algorithm provides directly the square root. PG’s algorithm gives first a procedure to extract a double square root, and then says that it should be halved. In other words, although they are grounded on the same idea, these two procedures differ in their intermediary steps. We will not expose their respective algorithms here, concentrating on what treatises tell us that commentaries do not and vice-versa.

This is how Ab gives the rule to extract square roots⁹¹:

Ab.2.4. One should divide, constantly, the non-square ⟨place⟩ by twice the square root|
When the square has been subtracted from the square ⟨place⟩, the quotient is the root in a different place||

Without a commentary the algorithm itself is hard to understand. Part of the difficulty springs from the fact that the verse states the algorithm, starting from its middle, emphasizing its iterative aspect. Another difficulty rises from Āryabhaṭa’s pun: a same name is given to squared (*varga*) digits and specific positions where digits are noted, “square positions”. This pun highlights exactly the mathematical idea behind the root extraction: “square places” of the decimal place value notation are positions where hints are given concerning the squaring of noted digits in order to produce the number at hand.

BAB and SYAB, will lift the difficulty raised by Ab’s pun, by introducing a new grid. Instead of considering square and non-square places, even and odd places are used. This is done by a simple

⁸⁹Why then were such procedures given? In a mathematical tradition where the correction of an algorithm is sometimes verified by inverting it, and finding the initial input, such a procedure which inverts the squaring procedure may have seemed useful. Solved examples in commentaries on these rules, all revert the squarings that were illustrated in the squaring procedure.

⁹⁰For general explanations on the different methods see (Datta, 1935, Volume I, 170-171), (Bag, 1979, 78-79).

⁹¹

bhāgaṃ hared avargān nityaṃ dviguṇena vargamūlena|
vargād varge śuddhe labdhaṃ sthānāntare mūlam||

See (K. S. Shukla, 1976, 36-37) for an explanation of the algorithm.

commentarial act, the substitution of one word by another. Thus, BAB states⁹²:

In this computation (*gaṇita*), the square (*varga*) is the odd (*viṣama*) place.

And SYAB⁹³:

In places where numbers are set-down (*vinyāsa*), the odd places have the technical name (*samjñā*) square.

We will come back to the different grids positions on the decimal place value notation. The commentarial act of substituting a name given in the treatise by another has two functions in this case: first, explaining the literal meaning of the verse; second, pointing to the mathematical meaning of the pun. More, this word substitution points to how, according to the commentators, the *sūtra* was composed: using a mathematical pun that pins down the mathematical idea behind the algorithm. If Ab gives the core mathematical idea of the algorithm, BAB and SYAB highlight it.

Ab's confusing pun was not taken up by PG⁹⁴:

**PG.24. Having removed the square from the odd term,
one should divide the remainder by twice the root that has trickled down to a
place**

⟨And⟩ insert the remainder on a line||

**PG.25. Having subtracted the square of that, having (re)moved the previous
result that has been doubled, then, one should divide the remainder. ⟨Finally⟩
one should halve what has been doubled.||**

PG's formulation of the algorithm avoids all puns: compared to Ab it is not so dense or confused. It however gives precise elements hinting to the concrete carrying out of the algorithm on a working surface. A line (*pañkti*) is evoked, the movement of trickling down as a drop of water (*cyuta*) is used to characterize the apparition of a partial, double root, digit by digit.

This is further developed by APG, which multiplies graphical depictions of partial roots, and evokes repeatedly operations carried above (*uparita*), below (*adhas*) and the fact that the partial double root

⁹²(K. S. Shukla, 1976, 52)

atra gaṇite viṣamam sthānam vargaḥ

⁹³(K. V. Sarma, 1976, p. 36, line 15).

samkhyā vinyāsasthāneṣu viṣamasthānāni vargasamjñāni

⁹⁴See (K. S. Shukla, 1959, 18 for the Sanskrit, 9-10 of the part in English for an explanation of the procedure as described in APG)

*viṣamāt padas tyaktyvā vargaṃ sthānacyutena mūlena|
dviḡuṇena bhajec cheṣaṃ labdham viniveśayet pañktau ||
tadvargaṃ samśodhya dviḡuṇaṃ kurvīt purvaival labdham|
utsārya tato vibhajec śeṣaṃ dviḡuṇīkṛtaṃ dalayet ||*

extracted slides like a snake (*sarpaṇa, sarpita*) to the next position⁹⁵. The procedure then is described in the details of how practically it is to be carried out in a working surface. The intricate way the positional system works is quite precisely indicated by APG. However no reference is made to the idea found in Ab's treatise evoking partial squares.

We see then the commentaries help us unveil how they perceived the different nature of Ab and PG as treatises. The emphasis is, on one side, on the idea behind the procedure (in Ab), on the other, on expressing all the different steps of the algorithm, including the fact that the double square is obtained on a separate line (for PG). And indeed, two different kind of treatises are involved here. Ab is a theoretical astronomical treatise while PG is explicitly devoted to practical mathematics (*vyavahāra*). Commentaries differ then according to the type of texts they comment. If they all include illustrated examples, APG is the only one to follow precisely how the different intermediary operations are carried out, even evoking the possibility for a doubled number to become bigger than 10, during the steps of the algorithm⁹⁶. On the other hand, neither BAB nor SYAB insist on these intermediary steps, highlighting on the contrary the essential idea behind the algorithm. PG concentrates on whole numbers, whereas the emphasis in SYAB and BAB is on the fact that the square root of fractions is the fraction of the square roots. The fact that commentaries adhere to the kind of text they are commenting, giving only what is appropriate in such circumstances, is especially clear in the case of SYAB: SYAB has read PG. SYAB actually quotes PG in this very verse commentary, not for the details of how the procedure is carried out on whole numbers, nor for the positioning of digits during the procedure, but for a rule concerning the square-root of fractions.

Thus commentaries are not systematically practical detailed explanations of the general cases formulated in the treatises. Commentaries follow closely what they deem is the aim of the treatise, explaining it, sometimes linking it to other considerations, but not going into details which would not be appropriate for the kind of treatise at hand. A commentary of a theoretical treatise will not detail the carrying out of a procedure, and reversely a commentary of a practical text, will not reflect on ideas, even if authors of commentaries know better. Furthermore, eventhought the non textual practice of tabular computations seems to be the realm of disposition and resolution parts of solved examples in commentaries, PG, as noted earlier, shows that treatises can also testify of these practices, although probably not in detail. So that style of commentaries depend on styles of treatises, or more precisely on how commentaries read treatises. An analysis of how commentaries, by word substitutions, has read the treatises can furthermore give us insights onto practices and thoughts that have until now not been analyzed: the use of the decimal place value as a formal notation.

3.2 Positional notation and extracting square roots

If the history of mathematics in the Indian subcontinent, has long insisted on showing that the decimal place value notation came from India, it reflected little on the concept different authors had of this

⁹⁵(K. S. Shukla, 1959, p.18-19 of the Sanskrit, p. 9-10 of the English version, both looked out together give Shukla's interpretation of how numbers are disposed and change during the algorithm, according to APG).

⁹⁶(K. S. Shukla, 1959, 18, line 15-16).

system, and in particular how they thought and used the idea of position. And indeed, for BAB, SYAB and APG the decimal place value is a conventional notation for which positions where digits are noted to make a number are an ordered set on a horizontal line⁹⁷. The important idea stressed with a great continuity by one author after another, is that a “place” (*sthāna*) does not exist alone, but only in relation to another, in an ordered relation. This is how a “place” then becomes a “position”, although there is no new Sanskrit word that expresses this conceptual change. Consequently, is this positional notation thought of as a positional *system*? A close look at the way commentators treat the extraction of square root procedures enables us to approach more closely their conception of position.

Let us recall how Ab gives the rule to extract square roots⁹⁸:

Ab.2.4. One should divide, constantly, the non-square ⟨place⟩ by twice the square root|
When the square has been subtracted from the square ⟨place⟩, the quotient is the root in a different place||

We have noted previously that one of the difficult aspects of this verse comes from a pun which makes us confuse which of the digits are squares (*varga*) and which of the digits are noted on “square positions”. Ab considers the decimal place-value notation as an ordered line of places, for increasing powers of ten. To this reading, he adds a new grid to qualify the positions, distinguishing powers of ten which are squares from those that are not squares. Ab’s readings of positions are concerned simultaneously with the mathematical dimension of the decimal place value notation and with the mathematical idea on which the algorithm rests. BAB followed by SYAB together help us understand Ab’s verse by giving new names to these positions. They both start from the decimal place value notation, but consider it outside of its mathematical signification. They count the different positions where digits are noted, starting on the right, from the lowest power of ten, and continuing on the left. All the even numbers of this enumeration indicate “even places”, and odd numbers, “odd places”. Since, 10^0 starts this enumeration, what Ab calls “square places”, BAB and SYAB call “uneven place”, and what Ab calls “non-square places”, BAB and SYAB call “even place”:

10^5	10^4	10^3	10^2	10^1	10^0
non-square place (<i>avarga</i>)	square place (<i>varga</i>)	non-square place	square place	non-square place	square place
6	5	4	3	2	1
even place (<i>sama</i>)	odd place (<i>viṣama</i>)	even place	odd place	even place	odd place

⁹⁷(Keller, 2006b).

⁹⁸

bhāgaṃ hared avargān nityaṃ dviguṇena vargamūlena|
vargād varge śuddhe labdhaṃ sthānāntare mūlam||

See (K. S. Shukla, 1976, 36-37) for an explanation of the algorithm.

Commentators then add to the ordered list of places that define the decimal place value notation their own grid. This grid considers the notation outside of its mathematical content, as a tabular form with a numbered list of items on a line. They apply a mathematical assessment, with odd and even numbers⁹⁹, to this formal way of looking at the decimal place value notation. This mathematical assessment is not directly related to the algorithm, until commentators link this grid to the one used by Ab, simply by substituting one word to another. Name substitutions are synthesized in Table 3.2.

Table 4: Names of places in the algorithm to extract square roots

Texts	Even powers of ten	Uneven powers of ten
Ab	<i>varga</i>	<i>avarga</i>
BAB	<i>viśama</i>	<i>sama</i>
PG	<i>viśama</i>	nihil
APG	<i>viśama</i>	<i>sama</i>
SYAB	<i>viśama</i>	<i>sama</i>

Places are used and qualified in different classifications: some underline their values, others their positions in an ordered line, others again pinpoint their mathematical qualities (as squares). These multiple qualifications point to the fact that all considered authors, do indeed use the decimal place value as a *system of positions* which can be qualified in as many different ways an algorithms requires.

We had seen previously that the commentarial act of substituting a name given in the treatise not only explains the literal meaning of the verse but also highlights the mathematical meaning of a pun. It also creates a new grid, a new system of positions, linking it to the one it has unravelled for the treatise.

PG uses the same vocabulary as BAB¹⁰⁰:

**PG.24. Having removed the square from the odd term,
one should divide the remainder by twice the root that has trickled down to a
place**

⁹⁹BAB brings it in through a linguistic analysis of the term *avarga*, noting: (K. S. Shukla, 1976, 52)

tasya eva nañā viśamatve pratisiddhe avargaḥ iti samam sthānam yataḥ hi viśamam samam ca sthānam

Since a non-square (takes place) when oddness is denied, by means of (the affix) *nañ* (the expression refers to) an even (*sama*) place, because, indeed, a place is either odd or even.

¹⁰⁰See (K. S. Shukla, 1959, 18 for the Sanskrit, 9-10 of the part in English for an explanation of the procedure as described in APG):

*viśamāt padas tyaktyvā vargaṃ sthānacyutena mūlena|
dviḡṇena bhajec cheṣaṃ labdhaṃ viniveśayet pañktau ||
tadvargaṃ saṃśodhya dviḡṇaṃ kurvīt purvaival labdham|
utsārya tato vibhajec śeṣaṃ dviḡṇāḡṛtaṃ dalayet ||*

⟨And⟩ insert the remainder on a line||

PG.25. Having subtracted the square of that, having (re)moved the previous result that has been doubled, then, one should divide the remainder. ⟨Finally⟩ one should halve what has been doubled.||

APG comments the verse regarding questions of place, as follows ¹⁰¹:

One should subtract a possible square¹⁰², from the *viṣama* place of the square quantity, ⟨in other words⟩ from what is called odd (*oja*), that is from the first, third, fifth, seventh etc., ⟨place⟩, from the places for one, one hundred, ten thousand, one million, etc. from the last among other places.

And considering the square root of 188624, it adds¹⁰³:

In due order starting from the first place which consists of four, producing the technical names (*saṃjñā karana*): “odd (*viṣama*), even (*sama*), odd (*viṣama*), even (*sama*)”.

Setting down:

sa	vi	sa	vi	sa	vi
1	8	6	6	2	4

In this case, the odd terms which are the places one, a hundred, ten thousands, consist of four, six and eight. Their last odd term is the ten thousand place which consists of eight.

APG completes as precisely as it can the mathematical background in relation to the decimal place value notation that the treatise just alludes to. Indeed, the anonymous commentator uses different syntactic expressions for a position, its value within a power of ten, the place it has in the row of numbers noted on the line, and the digit which is noted in this position. The values in power of tens that a position stands for are noted within a *tatpuruṣa* compound ending with *sthāna* and incorporating an inner enumerative *dvandva*, which gives the concerned powers of ten in increasing order (*ekaśatāyutasthānāni*,

¹⁰¹(K. S. Shukla, 1959, 18, line 10-12)

vargarāśer viṣamāt padād oṅkhyād ekatṛtīyapañcamasaptamāder ekaśatāyutaprayutādīsthānebhyo 'nyata-masthānād antyāt padāt sambhavinam vargaṃ tyajet

¹⁰²The adjective *saṃbhavin* conveys both the meaning “appropriate“ and ”conjectured”, the subtext understood is thus an “appropriately conjectured” square.

¹⁰³(K. S. Shukla, 1959, 18, line 19-22)

ānulomyena ekasthānāc catuṣkāt prabhṛti viṣamaṃ samaṃ viṣamaṃ samam iti saṃjñākaraṇam /

sa	sa	sa	vi	sa	vi
1	8	6	6	2	4

atra catuṣṣaḍaṣṭakāni ekaśatāyutasthānāni viṣamapadāni tebhyo 'yutasthānastham aṣṭakam antyaṃ viṣamapadam

“the places for one, a hundred, ten thousands”). The place it has in the row of numbers is referred to in several ways. APG numbers the positions, starting with one for the lowest power of ten and increasing successively. These are enumerated in a *dvandva* giving the ordinals of the concerned positions (*ekatṛtīyapañcamasaptamāder*, “for the first¹⁰⁴, the third, the fifth, the seventh, etc.). APG, following PG, reproduces then the *viśama* (odd) / *sama* (even) terminology found in BAB and SYAB. But PG and APG insist that positions are used within an ordered set, or *series* of numbers for which there is a first and a last term: PG uses the word *pada*, which is used for the terms of a series, and APG glosses *pada* with the expression *anyatamasthānāt antyāt*, “the last among all other places”. Finally noted digits are understood as tools to be worked with, within these positions. This may explain why names of numbers are given ending with the suffix *-ka* (*catuṣṣadaṣṭakāni*, “consists of four, six and eight”).

Thus a tightly knitted connection between commentary and treatise explains to us all the different ways in which a place becomes a position on an elaborate grid which rests not only upon the decimal place value notation, and on the algorithm to be carried out, but also within the formal system created by the notation itself: a line that can be ordered in many different ways.

To sum it up, different authors use the places of the decimal positional notation in different manners: Ab underlining their mathematical meaning (even powers of ten are square power of tens), BAB and SYAB linking these mathematical meanings to the formal notation of numbers (counting places from right to left and considering even and odd numbers), PG describing only this formal notation, and APG, as BAB and SYAB linking this formal notation to its meaning in relation to the decimal place value notation. Different lines on which the procedure to extract square root should be carried out are recalled, different grids described by APG: the horizontal expansion of the decimal place value notation is extended into a table, with operations conducted within columns and others within lines, as for other elementary arithmetical operations. A chronological perspective gives us maybe a historical evolution: it seems that over time the decimal place value notation, slowly took on a formal aspect, as a tabular form which could be used not referring systematically to what positions meant in terms of values of powers of ten.

Conclusion

Reflections on how commentaries read treatises in mathematics, can lead to conceptual insights into the practice of the decimal place value notation. A simple word substitution as used in BAB, SYAB and APG, has showed how the decimal place value notation is seen as a horizontal line in a table on which formal operations can be carried out.

Two different kind of *śāstras* have been studied here: one whose emphasis is on mathematical ideas, another on mathematical practices. The first belongs to a chapter of an astronomical treatise, the second belongs to a practical mathematical text. They each have different ways of describing algorithms. Studying different descriptive practices should enable further understanding of what was the use of these texts, what they were meant to convey.

¹⁰⁴ *eka* however is used here and not *prathāma*.

The perceived aim of treatises determines what commentaries decide they should do. Whether they will concentrate on ideas or on how the algorithm is carried out on a working surface. Treatises then can hint to “practical knowledge”, that commentaries can choose to spell out or not. However in all cases, the commentarial work consists in establishing relations, integrating what is hinted in the verse into a network of other systems.

If the ballroom dancing metaphor is taken up again then, the treatise seems to lead the dance, but this is what the commentator wants us to believe. Like a virtuose yet discrete partner, it uses all its techniques and knowledge to leave the limelight to the treatise. Such an attitude, which has its counter examples, helps us understand why a stylistic criteria to distinguish commentaries from treatises is so difficult to find.

A late tradition may have considered commentaries as fragmentary explanations and not full texts. The examples studied here show us at least a late seventeenth century tradition in South India considering commentaries as fragmentary explanations and not full texts. Looking at texts themselves, one can wonder whether they were made to be read, verse by verse, verse-commentary by verse-commentary, one after the other separately. In the case of the three commentaries on root extraction, the decimal place value notation and the rules to carry out elementary operations are used. If these are known, the commentary can be followed as if it was an autonomous text. Such an autonomous verse commentary reading may not hold for all algorithms. Nonetheless, different verse commentaries by different authors could have been used simultaneously, setting aside how a full commentary would provide a more integrated vision of what the treatise was about. But how much of this imagined partial reading of commentaries was originally there when authors wrote their commentaries and treatises? Should an oral culture of texts be imagined, where they are known as an integrated whole but can be quoted and mobilized in fragmentary ways?

Some information on who had text copied has been gathered on the way. In the case of SYAB scholarly astronomers, ritualist families and religious institutions of south India.

Coming back to how commentaries were read, a hypothetical evolution can be suggested: An early modern pandit tradition may have seeped into the way Colebrooke and other European scholars considered Sanskrit commentaries. Such attitudes could have mingled with a European tradition considering mathematical texts not for their textual characteristics but as just containing mathematical lore. The result being the kind of historiography, prevalent today when studying mathematical commentaries.

References

- Aklujkar, A. (2001). Paṇḍita and Pandits in History. In *The Pandit, Traditional scholarship in India* A. Michaels (Ed.), (p. 17-38). Manohar.
- Bag, A. K. (1979). *Mathematics in ancient and medieval India* (No. 16). Chaukhambha oriental research studies.
- Bayly, C. A. (1996). *Empire and information : intelligence gathering and social communication in India, 1780-1870*. Cambridge ; New York: Cambridge University Press.

- Bernard, A. (2003). Comment définir la nature des textes mathématiques de l'antiquité tardive? Proposition de réforme de la notion de 'Textes Deutéronomique'. *Revue d'Histoire des mathématiques*, 9, 131-173.
- Billard, A. (1971). *L'astronomie Indienne*. EFEO.
- Brahmagupta; Bhāskarācārya; Colebrooke, H. T. (1817). *Algebra, with Arithmetic and mensuration*. London: J. Murray.
- Bronkhorst, J. (1990). Vārttika. *Wiener Zeitschrift fuer die Kunde Suedasiens*, 34.
- Chemla, K. (1999). Commentaires, Editions et autres textes seconds: Quel enjeu pour l'histoire des mathématiques? Réflexions inspirées par la annote de Reviel Netz. *Revue d'Histoire des mathématiques*, 5, 127-148.
- Chemla, K. (2004). History of Science, History of Text: An Introduction. In *History of Science, History of Text* K. Chemla (Ed.), (p. vii- xxvii). Boston: Springer.
- Clark, E. C. (1930). *The Āryabhaṭīya of Āryabhaṭa*. University of Chicago Press.
- Datta, A. N., Bibhutibhushan & Singh. (1935). *History of Hindu mathematics* (Vol. 2). lahore: Motilal Banarsidass.
- Dikshit, S. B. (1896). *Bhāṭīya Jyotiḥśāstra* (Reprinted Poona 1931. Hindi translation b S. Jhārkhapḍī in Lucknow 1957. ed.). Poona.
- Dvivedin, M. S. (1902). Brāhmasphuṭasiddhānta and Dhyānagrahopadeṣādhyāya by Brahmagupta edited with his own commentary. *The paṇḍit*, XXIV, 454.
- Dvivedin, S. (1910). The Mahāsiddhānta of Āryabhaṭa. *Benares Sanskrit Studies*, 148, 149, 150.
- Dvivedin, S. (1910). The mahāsiddhānta of āryabhaṭa. *Benares Sanskrit Studies*, 148, 149, 150.
- Dvivedin, S. e. (1899). *Triśatikā by Śrīdharācārya*. Jagannath Mehta.
- Hayashi, T. é. (1995). *The Bakhshālī Manuscript. An ancient Indian mathematical treatise*. Egbert Forsten.
- Ikeyama, S. (2003). *Brāhmasphuṭasiddhānta (ch. 21) of Brahmagupta with Commentary of Pṛthudaka, critically ed. with Eng. tr. and Notes* (Vol. 38). New Delhi, India: Indian Journal of History of Science.
- Kāpadīā, H. R. (1937). Gaṇitatilaka, edited with introduction by H. R. Kapadia and commentary of Siṃhatilaka sūri. *Gaekwad Oriental Series*(78).
- Kaye, G. R. (March 1908). Notes on Indian Mathematics. no. 2. Āryabhaṭa. *Journal of the Asiatic Society of Bengal*, 8.
- Kejariwal, O. P. (1988). *The Asiatic Society of Bengal and the discovery of India's past*. Oxford University Press.
- Keller, A. (2006). *Expounding the mathematical seed, Bhāskara and the mathematical chapter of the Āryabhaṭīya* (Vol. 2 volumes). Basel: Birkh:ausser.
- Keller, A. (2006b). Comment on a écrit les nombres dans le sous- continent indien, histoires et enjeux.. In *Scéance du 17 Novembre 2006, Hommage rendu à Jean Filliozat* P.-S. Filliozat (Ed.), (chap. Comment on a écrit les nombres dans le sous- continent indien, histoires et enjeux.). Paris: Académie des Belles Lettres et Société Asiatique.

- Keller, A. (2007). Qu'est ce que les mathématiques? Les réponses taxinomiques de Bhāskara un commentateur, mathématicien et astronome du VIIème siècle. In M. Hert Phillippe; Paul-Cavalier (Ed.), *Sciences et frontières* (p. 29-61). Kimé.
- Kern, H. (1874). *The Āryabhaṭīya, with the commentary Bhaṭadīpika of Paramaśvara* (R. from Eastern Book Linkers, Ed.).
- Knudsen, L. T. (2008). *The Siddhāntasundara of Jñānarāja, A critical edition of Select Chapters with English Translation and Commentary*. Unpublished doctoral dissertation, Brown University.
- Netz, R. (1998). Deuteronomic texts: Late antiquity and the history of mathematics. *Revue d'Histoire des mathématiques*, 4, 261-288.
- Patte, F. (2004). *Le Siddhāntaśiromāni : l'oeuvre mathématique et astronomique de Bhāskarācārya = Siddhāntaśiromāniḥ : Śrī-Bhāskarācārya-viracitaḥ*. Droz.
- Pingree, D. (1970-1995). *Census of the exact sciences in sanskrit (CESS)* (Vol. 5 volumes). American Philosophical Society.
- Pingree, D. (1981). *Jyotiḥśāstra : astral and mathematical literature*. Wiesbaden: Harrassowitz.
- Plofker, K. (2009). *Mathematics in india*. Princeton University Press.
- Pollock, S. (2002). Introduction: Working Papers on Sanskrit Knowledge Systems on the Eve of Colonialism. *Journal of Indian Philosophy*, 30(5), 431-9.
- Pollock, S. (2006). *The Language of the Gods in the World of Men: Sanskrit, Culture and Power in Premodern India*. University of California Press.
- Raina, D. (1999). *Nationalism, Institutional Science and the Politics of Knowledge ; Ancient Indian Astronomy and Mathematics in the Landscape of French Enlightenment Historiography*. Unpublished doctoral dissertation, Göteborgs University.
- Raina, D. (2003). *Images and contexts: the historiography of science and modernity in india* (Vol. xi 234). New-Delhi: Oxford University Press.
- Rangacārya, M. (1912). *The Gaṇitasārasaṃgraha of Mahāvīra, edited with translation and notes*. Madras Government Publication.
- Rodet, L. (1879). Leçons de calcul d'Āryabhāṭa. *Journal Asiatique*, 7, 393-434.
- Sarma, K. V. (1976). *Āryabhaṭīya of Āryabhāṭa with the commentary of Sūryadeva yajvan*. New-Delhi, Inde: INSA.
- Sarma, S. R. (1966). *Grahaṇitādhyāya of the Mahāsiddhānta of Āryabhāṭa II*. Marburg.
- Sarma, S. R. (2006). Review of Expounding the Mathematical Seed. *Aestimatio*, 3, 142-146.
- Sen, S. N., Bag, A. K., & Sarma, R. S. (1966). *A bibliography of Sanskrit works on astronomy and mathematics*. National Institute of Sciences of India.
- Sengupta, P. C. (1927). *The Āryabhaṭīyam, translation*. , XVI.
- Shukla, K. S. (1959). *Pāṭīgaṇita of Śrīdharaācārya*. Lucknow: Lucknow University.
- Shukla, K. S. (1960). *Mahābhāskarīya, Edited and Translated into English, with Explanatory and Critical Notes, and Comments, etc*. Lucknow: University, Department of Mathematics Lucknow.
- Shukla, K. S. (1963). *Laghubhāskarīya, Edited and Translated into English, with Explanatory and Critical Notes, and Comments, etc*. Lucknow: Department of Mathematics and Astronomy, Lucknow

University.

- Shukla, K. S. (1972). Hindu Mathematics in the Seventh Century as found in Bhāskara I's commentary of the *Āryabhaṭīya*. *Gaṇita*, IV(2), 41-50.
- Shukla, K. S. (1976). *Āryabhaṭīya of Āryabhaṭa, with the commentary of Bhāskara I and Someśvara*. New-Dehli: Indian National Science Academy.
- Shukla, K. V., & Sharma, K. S. (1976). *Āryabhaṭīya of Āryabhaṭa, critically edited with translation*. New-Delhi: Indian National Science Academy.
- Srinivas, M. D. (1990). The Methodology of Indian Mathematics and its contemporary relevance. In *History of Science and Technology in India; Mathematics and Astronomy* (Vol. 1, chap.). Prakashan, Sundeep.
- Stoler, A. L. (2002). Colonial Archives and the Arts of Governance. *Archival Science*, 2, 87-109.
- Tubb, E. R., Gary A. ; Boose. (2007). *Scholastic Sanskrit, A manual for Students*. New York: American Institute of Buddhist Studies, Colombia University's Center for Buddhist Studies, Tibet House U S.